

# WINDSOR WINDOWS & DOORS

## PINNACLE CLAD OUTSWING DOOR

### (WZ3) (IMPACT)

INSTALLATION NOTES:

- ONE (1) INSTALLATION ANCHOR IS REQUIRED AT EACH ANCHOR LOCATION SHOWN UNLESS OTHERWISE NOTED.
- THE NUMBER OF INSTALLATION ANCHORS DEPICTED IS THE MINIMUM NUMBER OF ANCHORS TO BE USED FOR PRODUCT INSTALLATION OF THE MAXIMUM SIZE LISTED.
- INSTALL INDIVIDUAL INSTALLATION ANCHORS WITHIN A TOLERANCE OF ±1/2 INCH (I.E., WITHOUT CONSIDERATION OF TOLERANCES). TOLERANCES ARE NOT CUMULATIVE FROM ONE INSTALLATION ANCHOR TO THE NEXT.
- SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM(S). MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4 INCH. SHIM WHERE SPACE OF 1/16 INCH OR GREATER OCCURS. SHIM(S) SHALL BE CONSTRUCTED OF HIGH DENSITY PLASTIC OR BETTER.
- REFER TO SHEETS 3 - 7 FOR INSTALLATION DETAILS, ANCHOR SELECTION, AND ANCHOR REQUIREMENTS.
- SEALANT SHALL BE USED BETWEEN NAIL FIN AND SUBSTRATE.
- MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE WALL FINISHES, INCLUDING BUT NOT LIMITED TO STUCCO, FOAM, BRICK VENEER, AND SIDING.
- INSTALLATION ANCHORS AND ASSOCIATED HARDWARE MUST BE MADE OF CORROSION RESISTANT MATERIAL OR HAVE A CORROSION RESISTANT COATING.
- FOR HOLLOW BLOCK AND GROUT FILLED BLOCK, DO NOT INSTALL INSTALLATION ANCHORS INTO MORTAR JOINTS. EDGE DISTANCE IS MEASURED FROM FREE EDGE OF BLOCK OR EDGE OF MORTAR JOINT INTO FACE SHELL OF BLOCK.
- INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BY THE ANCHOR MANUFACTURER.
- INSTALLATION ANCHOR CAPACITIES FOR PRODUCTS HEREIN ARE BASED ON SUBSTRATE MATERIALS WITH THE FOLLOWING PROPERTIES:
  - WOOD - MINIMUM SPECIFIC GRAVITY OF 0.55.
  - CONCRETE - MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI.
  - GROUT FILLED CMU - STRENGTH CONFORMANCE TO ASTM C90.
  - STEEL - MINIMUM YIELD STRENGTH OF 33 KSI. MINIMUM 18 GA. WALL THICKNESS.
  - ALUMINUM - MINIMUM ALLOY 6063-T5. MINIMUM WALL THICKNESS 1/16" (0.0625").

GENERAL NOTES:

- THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE CURRENT FLORIDA BUILDING CODE (FBC), EXCLUDING HVHZ AND HAS BEEN EVALUATED ACCORDING TO THE FOLLOWING:
  - AAMA/WDMA/CSA 101/I.S.2/A440-11
  - ASTM E 1996-12
  - ASTM E 1886-13a
- ADEQUACY OF THE EXISTING STRUCTURAL CONCRETE/MASONRY AND 2X FRAMING AS A MAIN WIND FORCE RESISTING SYSTEM CAPABLE OF WITHSTANDING AND TRANSFERRING APPLIED PRODUCT LOADS TO THE FOUNDATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
- 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
- THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT IN NON-HVHZ AREAS.
- APPROVED IMPACT PROTECTIVE SYSTEM **IS NOT REQUIRED** ON THIS PRODUCT IN AREAS REQUIRING IMPACT RESISTANCE IN WIND ZONE 3 OR LESS.
- APPROVED IMPACT PROTECTIVE SYSTEM **IS REQUIRED** ON THIS PRODUCT IN AREAS REQUIRING IMPACT RESISTANCE IN WIND ZONE 4.
- DOOR FRAME MATERIAL:
  - WOOD
  - ALUMINUM 6063-T5
- DISSIMILAR METALS INCLUDING FASTENERS THAT MAY COME INTO CONTACT WITH ALUMINUM COMPONENTS SHALL BE PROTECTED IN ACCORDANCE WITH THE FBC.
- DESIGNATIONS "X" AND "O" STAND FOR THE FOLLOWING:

X: OPERABLE PANEL  
O: STATIONARY PANEL
- GLASS MEETS THE REQUIREMENTS OF ASTM E1300 GLASS CHARTS. SEE SHEET 8 FOR GLAZING DETAILS

TABLE OF CONTENTS

SHEET	REVISION	SHEET DESCRIPTION
1	B	INSTALLATION & GENERAL NOTES
2	B	ELEVATIONS
3	B	ANCHOR LAYOUTS
4	B	VERTICAL SECTIONS
5	B	VERTICAL SECTIONS
6	B	HORIZONTAL SECTIONS
7	B	HORIZONTAL SECTIONS (NARROW STILE)
8	B	GLAZING DETAILS, MULLION DETAILS & HARDWARE NOTES

DESIGN PRESSURE TABLE

TYP. OVERALL FRAME SIZE		TYP. OVERALL PANEL SIZE		DESIGN PRESSURE	INSTALLATION METHOD	MISSILE IMPACT RATING
MAX. WIDTH	MAX. HEIGHT	MAX. WIDTH	MAX. HEIGHT			
75.00"	94.875"	36"	92.25"	+50/-50 PSF	THROUGH FRAME, NAIL FIN & CLIP	LMI & SMI



WINDSOR WINDOWS & DOORS

900 S. 19TH STREET.  
WEST DES MOINES, IA 50265  
PH: (515)223-6660 FAX: (515)224-1938

TITLE: PINNACLE CLAD OUTSWING DOOR (WZ3)(IMPACT )

INSTALLATION & GENERAL NOTES


PREPARED BY:

BUILDING DROPS, INC.  
398 E. DANIA BEACH BLVD., STE. 338  
DANIA BEACH, FL 33004  
PH: (954)399-8478  
FAX: (954)744-4738  
WEB: www.buildingdrops.com



REMARKS	BY	DATE
NARROW STILE	YC	01.20
2020 CODE CHANGE	YC	01.20

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



HERMES F. NORERO, P.E.  
FLORIDA P.E. No 73778  
BUILDING DROPS, INC  
398 E. DANIA BEACH BLVD. # 338  
DANIA BEACH, FL 33004  
FBPE CERT. OF AUTHORIZATION No. 29578

FL #:  
**FL11517**

DATE: **06.25.2020**

DWG. BY: **YC** CHK. BY: **HFN**

SCALE: **NTS**


DWG. #: **WWD048**

SHEET:


**1**

OF 8

c:\users\luiz\desktop\building drops\projects\windsor windows and doors\cc-20-0118 - code change - fbc submittal - (version 7) code change\dwgs\011517\wwd048.dwg 8/13/2020 8:50 PM




ELEVATION  
BI-HINGE




ELEVATION  
STA-ACT

## QUALIFIED CONFIGURATIONS

NOTE:  
SIZES BELOW INDICATES  
MAXIMUM PANEL WIDTH FOR  
CONFIGURATIONS




## SIDELITE W/ NARROW STILE QUALIFIED CONFIGURATIONS



NOTE:  
SIDELITES USING 2 1/4\" STILE  
SHOULD NOT EXCEED 16\" OF  
PANEL SIZE WIDTH.

## QUALIFIED PANEL SHAPES



### NARROW STILE D.L.O. NOTES:

1. MAXIMUM DESIGN PRESSURE FOR NARROW STILE SIDELITE ON SHEET 2 SHOULD BE AS PER DESIGN PRESSURE TABLE AND A MAXIMUM D.L.O. OF 11.5\" X 102.50\".



## WINDSOR WINDOWS & DOORS

900 S. 19TH STREET.  
WEST DES MOINES, IA 50265  
PH: (515)223-6660 FAX: (515)224-1938

TITLE: PINNACLE CLAD OUTSWING DOOR  
(WZ3)(IMPACT )

ELEVATIONS


PREPARED BY: BUILDING DROPS, INC.

398 E. DANIA BEACH BLVD., STE. 338  
DANIA BEACH, FL 33004  
PH: (954)399-8478  
FAX: (954)744-4738  
WEB: www.buildingdrops.com



REMARKS	BY	DATE
NARROW STILE	YC	01.20
2020 CODE CHANGE	YC	01.20

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS TO BE USED WITH THIS DOCUMENT.



HERMES F. NORERO, P.E.  
FLORIDA P.E. No 73778  
BUILDING DROPS, INC  
398 E. DANIA BEACH BLVD. # 338  
DANIA BEACH, FL 33004  
FBPE CERT. OF AUTHORIZATION No. 29578

FL #: FL11517

DATE: 06.25.2020

DWG. BY: YC CHK. BY: HFN

SCALE: NTS


DWG. #: WWD048

SHEET:

2

OF 8

c:\users\luiz lopes\desktop\manager\building drops\projects\windsor windows and doors\cc-20-0118 - code change - fbc submittal - (version 7) code change\dwg\111517\wwd048.dwg 8/13/2020 8:50 PM



TYPICAL ANCHOR LAYOUT  
NAIL FIN

TYPICAL ANCHOR LAYOUT  
THRU FRAME

TYPICAL ANCHOR LAYOUT  
CLIP

FIN INSTALLATION ANCHOR TYPES					
ANCHOR DESCRIPTION	SUBSTRATE REQUIREMENTS	MIN. EMBEDMENT	MIN. EDGE DISTANCE	MAX. SPACING DISTANCE	NOTES
10d COMMON NAIL OR 11 GA. ROOFING NAIL X 2-1/2"	MIN. S.G.= 0.55 WOOD	1.5"	0.5"	HEAD: 8" O.C. JAMBS: 8" O.C. SILL: PER THRU FRAME INSTALLATION	--
#8 WOOD SCREWS	MIN. S.G.= 0.55 WOOD	1.5"	0.5"	HEAD: 8" O.C. JAMBS: 8" O.C. SILL: PER THRU FRAME INSTALLATION	--
#8-24 SELF-DRILLING OR SELF-TAPPING HWH SCREWS (GRADE 5)	STEEL: 18 GA. MIN., F <sub>y</sub> =33 KSI/ MIN. ALUM.: 1/8" MIN., 6063-T5 MIN.	3 THREADS PENETRATION PAST METAL STRUCTURE	0.5"	HEAD: 7" O.C. JAMBS: 8" O.C. SILL: PER THRU FRAME INSTALLATION	STEEL IN CONTACT WITH ALUM. TO BE PLATED OR PAINTED
FIN IS FASTENED TO DOOR WOOD FRAME WITH #8 X 1/2" WOOD SCREWS AT 8" O.C.					

THRU FRAME ANCHOR TYPES					
ANCHOR DESCRIPTION	SUBSTRATE REQUIREMENTS	MIN. EMBEDMENT	MIN. EDGE DISTANCE	MAX. SPACING DISTANCE	NOTES
3/16" Ø ULTRACON BY ELCO (F <sub>u</sub> =155 KSI, F <sub>y</sub> =177 KSI)	CONCRETE AT HEAD, SILL OR JAMBS F' <sub>c</sub> =3000 PSI MIN. C-90 HOLLOW/FILLED BLOCK AT JAMBS F' <sub>m</sub> =2000 PSI MIN.	1.75"	1.0"	HEAD: 8" O.C. JAMBS: 8" O.C. SILL: (1) 3" FROM ENDS & (1) 3" FROM CENTER + (1) 6" FROM CENTER	MAY BE USED THROUGH OPTIONAL 1X BUCKS, BY OTHERS
#10-24 WOOD SCREWS	MIN. S.G.= 0.55 WOOD	1.0"	0.75"	HEAD: 8" O.C. JAMBS: 8" O.C. SILL: (1) 3" FROM ENDS & (1) 3" FROM CENTER + (1) 6" FROM CENTER	--
#10-24 SELF-DRILLING OR SELF-TAPPING HWH SCREWS (GRADE 5)	STEEL: 18 GA. MIN., F <sub>y</sub> =33 KSI/ MIN. ALUM.: 1/8" MIN., 6063-T5 MIN.	3 THREADS PENETRATION PAST METAL STRUCTURE	0.75"	HEAD: 8" O.C. JAMBS: 8" O.C. SILL: (1) 3" FROM ENDS & (1) 3" FROM CENTER + (1) 6" FROM CENTER	STEEL IN CONTACT WITH ALUM. TO BE PLATED OR PAINTED

CLIP ANCHOR TYPES					
ANCHOR DESCRIPTION	SUBSTRATE REQUIREMENTS	MIN. EMBEDMENT	MIN. EDGE DISTANCE	MAX. SPACING DISTANCE	NOTES
3/16" Ø ULTRACON BY ELCO (F <sub>u</sub> =155 KSI, F <sub>y</sub> =177 KSI)	CONCRETE AT HEAD, SILL OR JAMBS F' <sub>c</sub> =3000 PSI MIN. C-90 HOLLOW/FILLED BLOCK AT JAMBS F' <sub>m</sub> =2000 PSI MIN.	1.75"	1.0"	HEAD: 8" O.C. JAMBS: 8" O.C. SILL: PER THRU FRAME INSTALLATION	MAY BE USED THROUGH OPTIONAL 1X BUCKS, BY OTHERS
#8-24 WOOD SCREWS	MIN. S.G.= 0.55 WOOD	1.0"	1.0"	HEAD: 8" O.C. JAMBS: 16" O.C. SILL: PER THRU FRAME INSTALLATION	--
#8-24 SELF-DRILLING OR SELF-TAPPING HWH SCREWS (GRADE 5)	STEEL: 18 GA. MIN., F <sub>y</sub> =33 KSI/ MIN. ALUM.: 1/8" MIN., 6063-T5 MIN.	3 THREADS PENETRATION PAST METAL STRUCTURE	0.75"	HEAD: 12" O.C. JAMBS: 16" O.C. SILL: PER THRU FRAME INSTALLATION	STEEL IN CONTACT WITH ALUM. TO BE PLATED OR PAINTED
CLIP FASTENED TO DOOR WOOD FRAME WITH (2) #6 X 3/4" SCREWS PER CLIP					



WINDSOR WINDOWS & DOORS

900 S. 19TH STREET.  
WEST DES MOINES, IA 50265  
PH: (515)223-6660 FAX: (515)224-1938

TITLE: PINNACLE CLAD OUTSWING DOOR (WZ3)(IMPACT )

ANCHOR LAYOUTS


PREPARED BY: BUILDING DROPS, INC.

398 E. DANIA BEACH BLVD., STE. 338  
DANIA BEACH, FL 33004  
PH: (954)399-8478  
FAX: (954)744-4738  
WEB: www.buildingdrops.com



REMARKS	BY	DATE
NARROW STILE	YC	01.20
2020 CODE CHANGE	YC	01.20

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS TO BE USED WITH THIS DOCUMENT



HERMES F. NORERO, P.E.  
FLORIDA P.E. No 73778  
BUILDING DROPS, INC  
398 E. DANIA BEACH BLVD. # 338  
DANIA BEACH, FL 33004  
FBPE CERT. OF AUTHORIZATION No. 29578

FL #:  
FL11517

DATE: 06.25.2020

DWG. BY: YC  
CHK. BY: HFN

SCALE: NTS

DWG. #: WWD048

SHEET:


3

OF 8







c:\users\luiz\desktop\manager\building drops\projects\windsor windows and doors\cc-20-0118 - code change - fbc submittal - (version 7) code change\dwg\011517\wvd048.dwg 8/13/2020 8:51 PM




**A 5** VERTICAL SECTION  
HEAD - CLIP INSTALLATION OPTION 1  
(JAMBS ARE INSTALLED THE SAME)



**B 5** VERTICAL SECTION  
HEAD - CLIP INSTALLATION OPTION 2  
(JAMBS ARE INSTALLED THE SAME)



**C 5** VERTICAL SECTION  
SILL - THRU FRAME INSTALLATION



**D 5** VERTICAL SECTION  
SILL - THRU FRAME INSTALLATION



**WINDSOR WINDOWS & DOORS**  
900 S. 19TH STREET.  
WEST DES MOINES, IA 50265  
PH: (515)223-6660 FAX: (515)224-1938


TITLE: PINNACLE CLAD OUTSWING DOOR (WZ3)(IMPACT)

VERTICAL SECTIONS

PREPARED BY: BUILDING DROPS, INC.  
398 E. DANIA BEACH BLVD., STE. 338  
DANIA BEACH, FL 33004  
PH: (954)399-8478  
FAX: (954)744-4738  
WEB: www.buildingdrops.com

REMARKS	BY	DATE
NARROW STILE	YC	01.20
2020 CODE CHANGE	YC	01.20

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS TO USE WITH THIS DOCUMENT



FL #: **FL11517**

DATE: **06.25.2020**

DWG. BY: **YC** CHK. BY: **HFN**

SCALE: **NTS**

DWG. #: **WWD048**

SHEET:

**5**

OF 8

900 S. 19TH STREET.  
WEST DES MOINES, IA 50265  
PH: (515)223-6660 FAX: (515)224-1938

HORIZONTAL SECTIONS


398 E. DANIA BEACH BLVD., STE.  
DANIA BEACH, FL 33004

PH: (954)399-8478  
FAX: (954)744.4738  
WEB: [www.buildingdrops.com](http://www.buildingdrops.com)



REMARKS	BY	DATE
NARROW STILE	YC	01.20
2020 CODE CHANGE	YC	01.20

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



HERMES F. NORERO, P.E.  
FLORIDA P.E. No 73778  
BUILDING DROPS, INC  
398 E. DANIA BEACH BLVD. # 338  
DANIA BEACH, FL 33004  
FBPE CERT. OF AUTHORIZATION No. 29578

DATE: 06.25.2020

DWG. BY: <b>YC</b>	CHK. BY: <b>HFN</b>
-----------------------	------------------------



SCALE: NTS

DWG. #: WWD048

SHEET:

6

DF 8





WINDSOR WINDOWS  
& DOORS

900 S. 19TH STREET.  
WEST DES MOINES, IA 50265  
PH: (515)223-6660 FAX: (515)224-1938


TITLE: PINNACLE CLAD OUTSWING DOOR (WZ3)(IMPACT )

HORIZONTAL SECTIONS  
(NARROW STILE)

 BUILDING DROPS, INC.  
209 E DANIA BEACH BLVD STE 220

DANIA BEACH, FL 33004  
PH: (954) 399-8478

**PH: (954) 399-8478**  
**FAX: (954) 744.4738**  
**WEB: [www.buildingdrops.com](http://www.buildingdrops.com)**

[illegible]

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



HERMES F. NORERO, P.E.  
FLORIDA P.E. No 73778  
BUILDING DROPS, INC  
398 E. DANIA BEACH BLVD. # 338  
DANIA BEACH, FL 33004  
FBPE CERT. OF AUTHORIZATION No. 29578

FL #: **FL11517**

DATE: 06.25.2020

DWG. BY: <b>YC</b>	CHK. BY: <b>HFN</b>
-----------------------	------------------------


SCALE: NTS

DWG. #: WWD048


SHEET:

7


OF 8




**BACK TO BACK MULLION**  
ACTIVE/ACTIVE




**BACK TO BACK MULLION**  
ACTIVE/INACTIVE



**BACK TO BACK MULLION**  
ACTIVE/INACTIVE



**PANEL DETAIL 1**



**GLAZING DETAIL 1**

**HARDWARE NOTES:**

**PINNACLE CLAD OS BI-HINGE DOOR**

(4) ADJUSTABLE HINGES INTO ASTRAGAL AT 7", 32-1/2", 57 1/2" & 83-1/2" FROM THE THRESHOLD. ACTIVE PANEL FIVE-POINT LOCKING SYSTEM WITH ENGAGEMENT POINTS AT 7", 38" & 74" ABOVE THE THRESHOLD WITH SHOOT BOLTS AT HEAD AND SILL. DEADBOLT LOCATED 34" ABOVE THE THRESHOLD. SPACING BETWEEN LOCK POINTS AND HINGES NOT TO BE EXCEEDED FOR ALTERNATE SIZES. SECONDARY ACTIVE PANEL WITH LEVER ACTIVATED SHOOT BOLTS AT HEAD AND SILL.

**PINNACLE CLAD OS ACTIVE-STATIONARY DOOR**

(4) ADJUSTABLE HINGES INTO ASTRAGAL AT 7", 32-1/2", 57 1/2" & 83-1/2" FROM THE THRESHOLD. ACTIVE PANEL MULTI-POINT LOCKING SYSTEM WITH ENGAGEMENT POINTS AT 7", 38" & 74" ABOVE THE THRESHOLD WITH SHOOT BOLTS AT HEAD AND SILL. DEAD BOLT LOCATED 34" ABOVE THE THRESHOLD. SPACING BETWEEN LOCK POINTS AND HINGES NOT TO BE EXCEEDED FOR ALTERNATE SIZES.



**WINDSOR WINDOWS & DOORS**

900 S. 19TH STREET.  
WEST DES MOINES, IA 50265  
PH: (515)223-6660 FAX: (515)224-1938

TITLE: PINNACLE CLAD OUTSWING DOOR (WZ3)(IMPACT)

GLAZING DETAILS AND HARDWARE NOTES

PREPARED BY: BUILDING DROPS, INC.  
398 E. DANIA BEACH BLVD., STE. 338  
DANIA BEACH, FL 33004  
PH: (954)399-8478  
FAX: (954)744-4738  
WEB: www.buildingdrops.com

REMARKS	BY	DATE
NARROW STILE	YC	01.20
2020 CODE CHANGE	YC	01.20

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

HERMES F. NORERO  
LICENSE  
No. 73778  
STATE OF  
FLORIDA  
PROFESSIONAL ENGINEER

HERMES F. NORERO, P.E.  
FLORIDA P.E. No 73778  
BUILDING DROPS, INC  
398 E. DANIA BEACH BLVD. # 338  
DANIA BEACH, FL 33004  
FBPE CERT. OF AUTHORIZATION No. 29578

FL #:	FL11517
DATE:	06.25.2020
DWG. BY:	CHK. BY:
YC	HFN
SCALE:	NTS
DWG. #:	WWD048
SHEET:	8